

**BID DIVISION HFH – 22B: Radon**

SUBMIT PROPOSAL TO:     HFH of Douglas County, Minnesota, Inc.  
                                  1211 N Nokomis NE, Alexandria, MN 56308

FOR:                         **Construction of Habitat for Humanity Homes**

EXCLUDED:

1. Electrical and controls wiring – Radon system

INCLUDED:

Provide all labor, materials, equipment, and site supervision to complete the radon installation as shown and specified, including but not limited to the following technical specification sections:  
22 05 02

ALSO INCLUDED:

1. Required permits, inspections, and certifications
2. Functioning systems upon the completion of construction
3. Compliance with all applicable Building Codes
4. All penetrations or core drilling required
5. Layout of all work
6. All labor and equipment to unload material
7. Verify existing site conditions
8. Coordination with other trades
9. This project is managed by Habitat. All contractors on this project are considered prime contractors. Coordination between trades and volunteers is to be considered part of this work scope.

**SECTION 22 05 02 - RADON**

**SCOPE OF WORK**

Complete Radon system including but not limited to:

- Furnish and install 3” PVC passive radon mitigation system from beneath slab through roof in utility room and insulated in attic, all in accordance with state and local codes and as otherwise indicated.

**END OF SECTION 22 05 02**