BID DIVISION DESCRIPTION

BID DIVISION HFH – 32A: LAWN SEEDING

EXCLUDED:
1. Dumpsters
2. Top soil
3. Final grading

INCLUDED: Provide all labor, materials, equipment and site supervision to complete the Lawn Seeding work as shown and specified, including but not limited to the following technical specification sections: 32 92 00

ALSO INCLUDED:
1. Tilling and leveling of soil as required
2. Application of Roundup or similar weed & grass killer to control exiting vegetation.
3. Protection of existing condition
4. Erosion control
5 Haul away stones, roots & other foreign matter
6. Coordination with other trades
7. This project is managed by HFHDC. All contractors on this project are considered prime contractors. Coordination between trades and volunteers is to be considered part of this work scope.

PRICING FORM:

Our Lump sum Base Bid for the work in Bid Division HFH – 32A is:

_____Dollars ($_____)

Name of Bidding Contractor:_____

Signed By:_____ Date:_____

SECTION 32 92 00

SCOPE OF WORK – LAWN SEEDING

Work of this Contract includes, but is not limited to, Lawn Seeding work as follows:

- Application of hydro seeding mix of not less than 1 lb of seed per 300 sq ft of surface over all designated lawn areas, approximately 7500 sq. ft. per lot.
- Preparation of seed bed shall be done by using a Harley Rake or Box Rake.
- Applicator shall provide needed or appropriate plant food at time of seeding and one post-emergence application.
- Removal of rocks, debris and waste materials unearthed by soil preparation process.
- Matting as required to control erosion.
- Any additional topsoil as may be required will be furnished by others.

Any questions concerning the requirements or work of this project may be directed to the address listed above or, by e-mail to: randy@hfhdouglascounty.org, 320-762-4255 ext 104.

END OF SECTION 32 92 00