

BID DIVISION HFH – 9A: DRYWALL HANGING

SUBMIT PROPOSAL TO: HFH of Douglas County, Minnesota, Inc.
1211 N Nokomis NE, Alexandria, MN 56308

FOR: **Construction of Habitat for Humanity Homes**

EXCLUDED:

1. Backing
2. Drywall material

INCLUDED: Provide all labor, incidental materials, equipment, and site supervision to complete the hanging of drywall as shown and specified, including but not limited to the following technical specification sections: 09 20 00

ALSO INCLUDED

1. Properly rated fasteners
2. Coordination with other trades
3. All work to be performed in compliance with MN building code R702.3
4. This project is managed by Habitat. All contractors on this project are considered prime contractors. Coordination between trades and volunteers is to be considered part of this work scope.

SECTION 09 20 00 - DRYWALL HANGING

SCOPE OF WORK

Work of this Contract includes, but is not limited to, the furnishing of all labor and materials as required for complete drywall hanging as follows:

- Measure, cut, and fit drywall sheets to accommodate wall and ceiling dimensions.
- Secure drywall sheets to framing members using appropriate fasteners, ensuring proper spacing and fastening methods.
- Install drywall with joints aligned properly and edges beveled or finished as needed.
- Cut openings for electrical outlets, switches, and vents precisely.
- Fit drywall around obstacles, windows, doors, and fixtures.

END OF SECTION 09 20 00