

BID DIVISION HFH – 32A: LAWN SEEDING

SUBMIT PROPOSAL TO: HFH of Douglas County, Minnesota, Inc.
1211 N Nokomis NE, Alexandria, MN 56308

FOR: **Construction of Habitat for Humanity Homes**

EXCLUDED: 1. Topsoil
2. Final grading

INCLUDED: Provide all labor, materials, equipment, and site supervision to complete the Lawn Seeding work as shown and specified, including but not limited to the following technical specification sections: 32 92 00

ALSO INCLUDED: 1. Tilling and leveling of soil as required
2. Application of Roundup or similar weed & grass killer to control exiting vegetation
3. Protection of existing condition
4. Erosion control
5. Haul away stones, roots & other foreign matter
6. Coordination with other trades
7. This project is managed by Habitat. All contractors on this project are considered prime contractors. Coordination between trades and volunteers is to be considered part of this work scope.

SECTION 32 92 00

SCOPE OF WORK

Work under this Section includes, but is not limited to:

- Application of hydro seeding mix of not less than 1 lb of seed per 300 sq ft of surface over all designated lawn areas, approximately 7500 sq ft per lot.
- Preparation of seed bed shall be done by using a Harley Rake or Box Rake.
- Removal of rocks, debris, and waste materials unearthed by soil preparation process.
- Matting to control erosion.
- Any additional topsoil as may be required will be furnished by others.

END OF SECTION 32 92 00